

ADDENDUM NO. 3

SEPTEMBER 7, 2022

**PREPARED BY SCHMIDT ASSOCIATES FOR:
AC THEATER RENOVATION
BSU PROJECT NO. 2022-008.01 AC
BALL STATE UNIVERSITY**

This Addendum consists of 2 Addendum pages and 1 attachment pages totaling 3 pages.

Acknowledge receipt of this Addendum by inserting its number on the Bid Form. Failure to do so may subject the Bid to disqualification. This Addendum is part of the Contract Documents.

Bidder is encouraged to verify with reprographer of record all Addenda issued (do not rely exclusively on third party plan room services).

PART 1 - CHANGES TO PRIOR ADDENDA

1.1 ADDENDUM NO. 2

- A. DELETE Section 015000 Paragraph 1.20.B

PART 2 - CHANGES TO THE PROJECT MANUAL

Modifications described herein shall be incorporated in the Project Manual. All other Work shall remain unchanged.

2.1 DIVISION 01 – GENERAL REQUIREMENTS

A. Section 015000 “TEMPORARY FACILITIES AND CONTROLS”

- 1. DELETE AND REPLACE Paragraph 1.20.A as follows:
 - A. “Temporary site fencing and gate(s).
 - 1. Provide 6 feet high chain-link fence around construction site, either fixed or movable.
 - 2. Construction: Commercial grade chain link fence.
 - a. Provide at least one vehicular gate, same height as perimeter fence, with a minimum 10 feet opening. Provide additional gates as indicated or necessary for site and personnel access.
 - b. Chain link fabric: 9 gauge by 2-inch galvanized steel wire fence fabric.
 - c. Accessories: Provide appropriate brackets and hasp to accommodate an Owner-furnished padlock.

- d. Windscreen: Provide black HDPE windscreen with hemmed edges and steel grommets.
3. Fixed Fencing:
 - a. Install fixed fencing by driving line posts in the ground a minimum of 24 inches. Space posts no more than 8 feet apart.
 - b. Posts: 2-inch galvanized steel tubing.
 - c. Horizontal tubes: 1-1/2 inch minimum galvanized steel tubes.
4. Movable Fencing:
 - a. Fabricate fencing with welded 1-3/8 inch galvanized steel tube frames with intermediate horizontal and vertical posts.
 - b. Provide tip-resistant movable panel stands with appropriately sized sandbags or other movable weights, sufficient to prevent displacement by weather or pedestrian contact. Provide additional counterweight at gate posts.
 - c. Connect adjacent panels with a minimum of 2 saddle clamps.
5. Maintain fencing for the duration of the project. Do not remove until approved by the Owner."

PART 3 - CHANGES TO THE DRAWINGS

Modifications described herein shall be incorporated in the Drawings. All other Work shall remain unchanged.

3.1 DRAWING SHEETS: ADDITIONS, DELETIONS AND REPLACEMENTS

DRAWING NO.	INDICATE ACTION: REPLACE (R), ADD (A), DELETE (D)
E-SERIES DRAWINGS	
E-603	DELETE AND REPLACE

END OF ADDENDUM 3

